City of Detroit Housing And Revitalization Department Housing Service Division

Two Woodward Avenue, Suite 908 Detroit Michigan 48226

RESIDENTIAL REHABILITATION PROJECT BIDDING INSTRUCTIONS

The City of Detroit Housing And Revitalization Department Housing Services Division (HRD) is accepting Bids for INSTRUCTIONS TO BIDDERS:

- 1. This is a Microsoft Excel software document. All line item fields must be completed. Note: Contractor
- 2. Bids will only be accepted from bidders who attend a mandatory Project Walk-Thru at the property
- 3. The Bid Proposal Documents must be completed and returned to HRD or GS Group, LLC., at 17800
- 4. Bids will not be accepted without an authorized signature which is on file with GS Group, LLC.
- 5. Bid proposal must be submitted in a 10" X 13" envelope (one bid proposal per envelope) properly labeled <u>City of Detroit Housing And Revitalization Department or email to HRDHomeRepair@detroitmi.gov</u>

City of Detroit Housing And Revitalization Department CHIP/City Wide /Child Help Lead & 0% Programs

EXHIBIT A

	Two Woodward Ave Detroit Michiga		
DATE	BID PROPOS	AL FOR:	
Case No.:	30367	Program Name MICHID	
Property Owner:	Danielle Estes	Program Name: MICHIP Phone #: 313-399-2041	
Property Address:	1772 Seyburn	Alternate Phone #:	
City, State Zip	Detroit, Michigan 48214		
		Historic Designation: Yes	
	Attentio	n: The Housing And Revitalization Dept.	
		Two Woodward Avenue, Suite 908	
		Detroit, Michigan 48226	
For Rehab	pilitation/Repair of the property located at:		
	TL -		oit, Michigan
		ontractor Inc.	(General Contractor)
proposes to do all of the the sum of	work as set forth in the plans and/or work specificati Nighty Eight thousand four hun-	1-1 100	28,400 .00)
PROVIDED that the bid	The proposed Walk-Thru for this shall be accepted by the OWNER or his/her agent w	ithin 30 days from receipt of said hid and that	AT 11:00 a.m.
The bids will be opened	at 10:30 a.m. on the bid due date.	t. no later than 10:00 AM on:	3/17/2021 Due Date
By:	Work specification dated:	3/2021	
	Authorized Signature	The second secon	
	Jozef Contractor Inc		
	Name and Title (Print)	Will the second continuous second	
	17245 Mt Elliott		
	Address		
	Detroit Mi 48212		
	City, State, Zip Code		
	586-604-5210		
	Phone		
	313-427-0154		
	Fax		
	City of Detroit Housing And Re	vitalization Department	EXHIBIT A
	Housing Service		
	Two Woodward Avenu		
	Detroit Michigan	48226	
Case No.:	30367	D	
Property Owner:	Danielle Estes	Program Name: MICH	
Property Address:	1772 Seyburn	Phone #: 313-3 Alternate Phone #: -	99-2041
City, State Zip	DETROIT, MI 48206	Historic Designation Yes	
Underwriter/ Spec. Compliance Inspector	Diana Patillo	Phone No. 313-224-4488 Fax	x No.
compliance inspector	Martha H. Delgado	Phone No. 313-224-9081 Fax	No. 313-224-9149

Risk	Assessor
Date	Writton

GS Group-Sheresse Smith	Cert. No. P-05920	Phone No.	313-279-0449
November 15, 2019	Revised 12/17/2019	3/3/2021	-
	THE THE THE TENT OF THE TENT O	0/0/2021	

WORK SPECIFICATION

Unless specifically excluded, all workmanship and materials are to fully comply with all applicable building codes and meet the minimum NOTE:

All line items identified by LHR are Lead Hazzerd Demodiation items and should be hid accordingly.

COST	Component	НН	LHR	azard Remediation items and should be bid accordingly. Floor/Room/ Area
		7 14 1	MAT 11 3	INTERIOR
***************************************				FOYER-Item 1
\$1,100	Ceiling		LHR	Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
				DINING ROOM-Item 2
\$650	Wall D Door Casing & Stop & Wall C Door Casing		LHR	Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
				KITCHEN 1ST FLOOR ITEM #3
3,900.00	Faucet-Kitchen-Wall C Lower CabinetC Wall		LHR	Remove the existing faucet/fexture and replace with new. Install lead free Delta Kitchen Sink Faucet model number 100 DST or 100 BH-DST for non sprayer locations. Or model number 400 DST,400BH-DST ,400 DST-A or 400 DST-L for sprayer equipped locations the shut off valves. Components to be from Lead Free product lines or non-metal. (Must meet minimum NSF/ANSI 61-G and NSF/ANSI 372). Faucet documents/papework to be presented to RFC for verification of proper components. All aerator keys/wrenches to be provided to homeowner. Contractor responsible to ensure proper drainage as of job completio-verify before staring work. Remove existing wood cabinets. Install new pre-finished manufactured base cabinet per owner selection. Install Formica or plastic laminate countertop with 4" backsplash Install a new (double) bowl stainless steel sink, complete, trap, water supply lines, and cutoff valves to code. Make all necessary wall repair prior to installing new cabinets to ensure sound and stable wall surface. Perform paint stabilization where cabinets were removed and/or replaced.
900.00	Walls B,C		LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
700.00	Wall C Door Casing & Jamb		LHR	Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
600.00	Wall A Closet Casing, Rail, Shelf, Walls			Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
				LIVING ROOM-Item #4
\$1,100	Walls- A,B &C, Baseboard, Crown Molding,		LHR	Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
	Wall B Door Casing & Stop		LHR	Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.

	Wall C Door Casing & Hinge	LHR	Perform substrate stabilization Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$450		LHR	ENCLOSED PORCH-Item #5
§ 1,500.00	Ceiling, Walls,Baseboard, Wall D Window Sill,Wall B Window Sill,Wall A DoorJamb & Stile		Perform substrate stabilization. Repair all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
			STAIRWELL 1-Item #6
1 700 00	<u>Walls</u>	LHR	Perform substrate stabilization. Repair all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
5 1,700.00	Wall A Door Casing & Panel	LHR	Remove and dispose of existing door casing, interior door and jamb. Install new equivalent pre-hung hollow-core wood (or molded) door and stop with lock set. Install new equivalent casing to both sides. Must match existing architecture, when possible. Caulk all casing seams with low VOC caulk. Homeowner responsible for finish painting.
750.00	Wall B Door Panel	LHR	Remove and dispose of existing door casing, interior door and jamb. Install new equivalent pre-hung hollow-core wood (or molded) door and stop with lock set. Install new equivalent casing to both sides. Must match existing architecture, when possible. Caulk all casing seams with low VOC caulk. Homeowner responsible for finish painting.
5 750.00	Stair Stringer	LHR	Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature a time of application.
5 1,100.00 5 950.00	Wall C Closet Ceiling,Baseboard,Do or Jamb,B & D Walls		Perform substrate stabilization. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature a time of application.
			BEDROOM 1-Item #7
S 900.00	Baseboard, Wall C Window Casing & Sill, Wall D Window Sill & Sash, Wall B & C Door Casings & Stiles	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. We scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
5 750.00	Wall B Closet D Wall, Window Casing & Sill (A-wall) Window Casing & Sill(C-wall) Baseboard, Door casing & Stile & Stop	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
			BEDROOM 2-Item 8
	Wall A Window 1 Sill, Wall A Window 2 Sash & Casing,	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
950.00			

	Wall C Closet B,C,D Walls, Rail,Baseboard,Door Casing & Door Jamb	LHR	Perform substrate stabilization. Repair or replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$ 1,300.00			DEDDOOM A
\$ 750.00	Wall A Window 1 Sash & Sill, Wall A Window 2 Casing & Sash	LHR	BEDROOM 3-Item 9 Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
	Wall C Doors 1 & 2 Casing & Jamb		Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$ 750.00 \$ 950.00	Wall C Closet Shelf, Door Casing Baseboard, Window Cashing & Sash (Wall B)	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
			BATHROOM 1-Item 10
\$ 750.00	<u>Faucet</u>	LHR	Remove the existing faucet aerator and replace with new.Install new lead free Delta Lavatory Faucet (allowance (\$450.00) Lavatory Faucet Model: B2596LF or B3596LF2(Windemere Collection). Include all required fixture connections/accessories such as new pop up assembly (if needed) and shut off valves. 1. Components to be from LEAD FREE produc lines or non-metal. Must meet minimum: NSF/ANSI61G & NSF/ANSI372. Faucet documents/papework to be presented to RFCfor verification of proper components. All aerator keys/wrenches to be provided to homeowner. Contractor responsible to ensure proper drainage as of job completioverify before staring work.
\$ 1,100.00	Walls, Wall Trim,Wall C Window Sash	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
	Annanannanananananananana		HALLWAY-Item 11
\$ 1,300,00	Ceiling, Walls,Baseboard,	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
3 1300.00	Wall A Doors 1&2 Casing & Stops	IHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$ 750.00		· · · · · · · · · · · · · · · · · · ·	
\$ 750.00	Wall C Door I Casing & Jamb, Wall C Doors-2 & 3 Casing & Panels	LHR	Remove and dispose of existing door casing, interior door and jamb. Install new equivalent pre-hung hollow-core wood (or molded) door and stop with lock set. Install new equivalent casing to both sides. Must match existing architecture, when possible. Caulk all casing seams with low VOC caulk. Homeowner responsible for finish painting.
\$ 1,400.00	Wall D Cabinet Door,	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
	Drawer 1,2,3,& Stop		
	I lanna		STAIRWELL 2- Item 12

٧.

		Walls (Plaster)	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$ \$	950.00 750.00	Wall Trim (Wood/Olive)	LHR	Perform substrate stabilization. Repair or replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$	550.00	Wall B Ledge	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$	950.00	Stair Stringer & Riser	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
.,,,,,,		nannan manan m		STAIRWELL 3-Item #3
\$	900.00	<u>Ceiling, Walls</u>	LHR	Perform substrate stabilization. Repair or replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
S	900.00	Wall C Door Casing & Jamb, Wall A Door Casing	LHR	Perform substrate stabilization. Repair or replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
.,,,,,,		annina aan aa		BASEMENT-Item #15
\$	950.00	Wall A (Brick)	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
				1 AUNIDRY DOOM (B A) 14 419
\$	950.00	Wall B (Brick) -Wall B Windows 1,2,3 Casings & Sashes; Wall C Window Sash	LHR	LAUNDRY ROOM (Basement)-Item #18 Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
				BATHROOM (Basement)-Item #16
\$	450.00	Wall A Door Panel	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate install new drywall. Wet scrape, prime any bare areas and repaint these surfaces with two coats of enamel paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application.
\$	750.00	Lead Clean	LHR	ENTIRE HOUSE-FINAL CLEANING FOR LEAD ENTIRE HOUSE CLEANING-FINAL CLEANING FOR LEAD Clean entire house including all floors (include main basement floor), window sills & troughs according to the established lead safety regulations (i.e. HEPA vacuum and wet cleaning procedures). EXTERIOR: Perimeter paint chips/debris & other work areas. Note: this includes Paint Chips Prior to the start of work, and any highly visible area of paint chip debris. General Debris-House Perimeter Only Note: this would include other debris such as generic trash, bottles, etc. along the Perimeter of House or other work areas.
C	OST			EXTERIOR -HISTORIC
100 000	JOI			(20 Year EXTERIOR PAINT)- COMPONENTS

WINDOW COMPONENT (ALL ORIGINAL WOOD) Total 29	LHR	Remove the interior stops and save (or discard and replace with new RFC choice). Remove the upper and lower window sashes. Perform substrate stabilization, wet scrape and fully apply Eco-Bond Lead Defender, or equivalent to all painted surfaces of the jambs and troughs. Determine track shape, most wood sashes have either a square-shaped groove or a "V" shaped groove. Install the proper jamb liner so that it extends the full length of each side jamb. Install jamb liners to manufacturers' recommendations. Reinstall the sashes and stops. If stops are damaged, broken or missing, install new stops that closely match existing in like and kind. Total (29)
Cellar Windows	LHR	Remove and dispose of basement windows and all framing. Install new framing to receive glass block windows complete with metal vent. Mortar and caulk (low VOC) to provide secure and weather tight fit. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris, including but not limited to roofs and eaves troughs. Total (7)
Wall A Roof Dormer Components- & Roof Components	LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.
Walls (Concrete / Yellow (2nd Floor)	LHR	Repair all damaged substrate. <i>This must comply with Historic Preservation guidelines i.e. match the size, design, proportions, profile and whenever passible, materials of the existing shingles</i> . Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.
Roof Replacement Include Front porch		Remove all existing shingles down to the roof boards. Install 7/16 inch Oriented Strand Board. Install new Dimensional 30 year asphalt shingle roofing, including 15 lb. asphalt saturated felt, over entire roof, ice and water shield at all eaves and valleys, and aluminum T-Drip at all edges of roof. (approx. 20 Sq.) Match to existing in color and design
Roof Rear Enclosed Porch		TORCH-DOWN BITUMINOUS ROOFING: (3Sq)Remove all existing roofing down to the roof boards.Install (1/2)-inch thick exterior grade plywood over entire deck. (approx. Sq.Ft.) Install metal drip edge on perimeter of deck. Install new torch-down bituminous roofing over the entire deck. Install metal flashing, properly sealed, where the deck roofing abuts dwelling.
Gutters/Downspouts		Install new aluminum gutters on entire dwelling. (approx. Lin.Ft) Install new rectangular aluminum downspouts. (approx. Lin.Ft)
Roof Components	LHR	Perform substrate stabilization. Repair all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.
Wall C &D Trim (Brick/White)	LHR	Perform substrate stabilization. Repair all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.
	Cellar Windows Cellar Windows Cellar Windows Wall A Roof Dormer Components- & Roof Components Walls (Concrete / Yellow (2nd Floor) Roof Replacement Include Front porch Roof Rear Enclosed Porch Gutters/Downspouts Roof Components	COMPONENT (ALL ORIGINAL WOOD) Total 29 LHR Wall A Roof Dormer Components & Roof Components LHR Walls (Concrete / Yellow (2nd Floor) LHR Roof Replacement Include Front porch Gutters/Downspouts Roof Components LHR Wall C &D Trim LHR

S	450.00	Wall C Door Components -Exterior (2nd Floor)		LHR	Perform substrate stabilization. Replace all damaged or rotted substrate. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, pair chips and debris.	
S	800.00	Wall A Door Jamb, Casing & Lintel	an ann an	LHR	Remove and keep existing door. Remove existing stop. Plane all edges of door to prevent friction/impact surfaces. Perform substrate stabilization on doors and all remaining door trim. Wet scrape and fully apply Eco-Bond Lead Defender (or equivalent) to doors, jamb and interior/exterior casing. Install new equivalent primed stop. Re-install existing door. Replace weatherstripping if necessary to provide an airtight seal.	
\$	800.00	Wall A Door Jamb, Casing & Lintel		LHR	Remove and keep existing door. Remove existing stop. Plane all edges of door to prevent friction/impact surfaces. Perform substrate stabilization on doors and all remaining door trim. Wet scrape and fully apply Eco-Bond Lead Defender (or equivalent) to doors, jamb and interior/exterior casing. Install new equivalent primed stop. Re-install existing door. Replace weatherstripping if necessary to provide an airtight seal.	
\$	1,500.00	Wall A Porch Ceiling, Ceiling Beam & Columns & Water Spout		LHR	Perform substrate stabilization on porch ceiling ,ceiling beam. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.	
\$	750.00	Wall D Window 1 Casing & Sash		LHR	Perform substrate stabilization on porch ceiling ,ceiling beam. Wet scrape, prime any bare areas and repaint these surfaces with two coats of exterior grade, 20 year paint. Apply all products to manufacturer's specifications for application and proper surface temperature at time of application. Ensure all exterior, horizontal surfaces are free of visual dust, paint chips and debris.	
		,			GARAGE	
\$	1,900.00	Demo Garage		LHR	Demolish and dispose of garage. Terminate all utilities at source. Foundation and concrete to remain. Homeowner to clear ALL belongings in garage prior to work beginning.	
\$	450.00	C/O DETECTORS	Ш		CARBON MONOXIDE DETECTOR-INSTALL (HH) Install Underwriters Laboratory (UL)-certified, Carbon Monoxide Detector. Install near sleeping areas. Install at recommended height per manfacturer. Do not install on ceiling. Test detector upon installation. (Allowance of \$47.00 per Detector (product and installation). First floor - Hall and Top of basement; Second Floor Hallway)	
\$	450.00	Sealed Smoke Detectors	<u>НН</u>		SEALED SMOKE DETECTORS- INSTALL (HH) - Furnish & install Sealed Smoke Detectors with 10 -yeas lithium battery. Replace old existing detectors with new detectors per City of Detroit Code. Allowance of \$51. per Detector (product and installation)	

Construction Repairs Sub-Total:

\$ 1,200.00

BUILDING PERMIT (All other paquired electrical, heating, and plumbing permit cost must be included in

TOTAL COST \$

Healthy
Homes Cost:

Emergency Repair Cost:

Lead Hazard Remediation Cost:

The Contractor shall remove all con	struction and demolition debris related to the	work performed during rehabilitation as it is
		1 0-1/1
OF:	Jozef Contractor Inc	Jones OVIII
······································	Company Name	Company Owner Signature
COMMENTS:		
Н	omeowner Acknowledg	gement Form
Rehab Address:	1772 SEYBURN	
1		or and and
By my signature below, I acknowle	edge that I have reviewed the work specificat	ion with a representative of the City of Detroit
Initial Appropriate Box		
	, , , , , ,	actors, pre-approved by the City of Detroit Housing id on the repairs to my property as identified on the
I further agree to accept the lowest	bidding qualified contractor as determined by	by Housing And Revitalization Department's
SIGNED:		
	Owner's Signature	Date
SIGNED:		
	Owner's Signature	Date
WATERCO DV HDD		
WITNESS BY HRD		Date