



## **PROPOSAL**

**DATE:** 7-28-2020

**RE:** Broderick

**PH:** 313-587-3979

### **CONTRACTOR:**

**ATTN:** Luis Ramirez

**Chamberlain Glass & Metal, Inc.** is pleased to submit this proposal for the above-mentioned project. We will supply and install items listed below.

#### **Aluminum Storefront & Pair of Doors:**

- Qty 2 single doors in one opening with side lites, 2 single doors separate, 1 pair of doors with side lites.
- Oldcastle Center Set Storefront 2" x 4 1/2" system Dark Bronze
- Oldcastle Medium stile doors Dark Bronze
- Glass 1" O.A. 1/4" Clear 1/2" Air 1/4" Neutral 78/65

#### **Hardware for Storefront:**

- Hardware finishes furnished as dark bronze and/or the equivalent.
- Cylinder allowance of \$125.00 each included.
- Final cores and/or keying not included.
- Card reader by security contractor.
- Wiring diagrams by security contractor.
- Hardware sets we made attached.

#### **Bipart Slider:**

Besam SL500 Sliding Door System with Full Breakout

Equipment: OC

Type: Full Breakout

Handing: Bi-part

Door Stile: Narrow Stile

Finish: Dark Bronze Anodized

Overall Frame Width: 168

Mounting Height: 92

Clear Door Opening Width: 72.25

Clear Door Opening Height: 84

Frame Type: Jambs Frame Depth: 4-1/2"

Jambs Glass Stop: 1/4" Glass Stop, 1/4" clear tempered glass

Bottom Rail: 10" Bottom Rail

Sensor: Motion & Presence Sensor

Lock: No Lock or Lock Prep

Guide System: Pin Guide / Surface Track  
 Mode Selector: 5-Position Switch - Key  
 Muntins: Muntins A/L & S/L  
 Muntins Thickness: 4" Muntin  
 Muntin Quantity: (1) Muntin  
 Centerline of Muntin bar: 41.25  
 Panic Exit Devices: AR F86 Flush Panic  
 Electric Lock: Fail Secure Electric Lock  
 Security Switch: Security Switch  
 Carrier Wheels: Heavy Duty Carrier Wheels  
 Sweeps: Concealed Sweep Active Leaf & Sidelight  
 Configuration: Standard  
 1year warranty parts and labor

**Sealant:**

- As it relates to above sections.

**FOR THE SUM OF ..... \$ 69,000.00**

**ALT ADD FOR DEMO no Dumpster.....ADD \$ 4,500.00**

Excludes:

Bond, DEMO, Steel, Wood blocking,  
 Final cleaning, Fire Rated Glass  
 Shop Drawings, Testing, Permits, PE Calculations  
 Dumpster, sidewalk protection, Sidewalk closures

**Exclusions for Sliding Door:**

1. Excludes: • 110 volt electrical service to operator header,  
 Prepared Opening to accept package(s), Removal and disposal of existing doors , Painting,  
 patching and repairing of floors, walls and ceilings, Wiring and electrical equipment required to  
 interface with door operator/controls and any other electrical control/monitoring systems either  
 existing or supplied by others

Respectfully Submitted  
 Jason Chamberlain  
 Chamberlain Glass & Metal, Inc.

**QUOTE IS VALID FOR 60 DAYS**

750 Fred W. Moore Hwy. St. Clair MI 48079 PH: 810-326-1000 FAX: 810-326-1001