



July 5, 2022

Barton Malow Company
26500 American Drive
Southfield, Michigan 48034

Attention: Ms. Kara Martini

Regarding: Marine Corp Reserve Center
Detroit, Michigan 48235



Dear Ms. Martini:

RAM Construction was requested to inspect and issue a thorough scope of work that we recommended implementing to restore the exterior masonry and stone at the above-mentioned facility. Please see below description of masonry building envelope restoration scope.

1. Decorative Limestone:

- Remove and replace limestone mortar joints 100%
- Replace severely damaged limestone pieces with salvaged limestone from the south portion of the building that is being demolished.
- Install “dutchman” limestone pieces where stone is beyond patching
- Patch, rout and seal cracks as necessary
- Remove and replace skyward facing joints, new sealant will be installed with a color to be chosen by owner

2. Clean Entire Façade:

- Remove all graffiti on all elevations
- We will pressure wash the entire masonry and limestone façade
- All staining and dirt sediment will be removed
- A mockup will be approved by the owner before any production cleaning takes place



Typical area exhibiting limestone spalls, joint failure, as well as stones in need of being reset



Typical area exhibiting limestone joint failure as well as stones in need of being reset



Area of wall identified as needing new limestone panels installed at existing building elevation to remain



Area beyond repair, new stone will be furnished and installed to match existing

We look forward to hearing from you soon, it will be our pleasure to assist in any way that we can. If you have any questions or concerns, please feel free to contact me at any time.

Sincerely,
RAM Construction Services of Michigan, Inc.


Andrew Sandzik