



August 1, 2022

Jonah Raduns-Silverstein
Director of Operations
Detroit Sound Conservancy
projects@detroitssound.org

RE: Blue Bird Inn - 5021 Tireman Detroit MI. Front elevation masonry facade restoration

- ❖ Mobilize the front elevation of the masonry facade with proper scaffolding and equipment.
- ❖ Remove all deteriorated stone from the front masonry facade including all stone belts, coping stone and ornate stone pieces.
- ❖ Fabricate new limestone units and Install using proper methods back to its original profile.
- ❖ Remove all loose, missing or damaged brick units and replace with new brick units matching as close as possible.
- ❖ Tuck point all missing and deteriorated mortar joints of the masonry on the entire front elevation.
- ❖ Prepare control joints of new stone coping caps and install new backer rod and sealant.
- ❖ Wash all areas where work was performed.
- ❖ Clean up of the jobsite.



This proposal includes all labor, materials and taxes and will remain in effect for sixty (60) days from the above date.

Sincerely,

Pat Curry
JMD Building Restoration
pat.curry@jmdbuildingrestoration.com

JMD Building Restoration LLC
18370 Fitzpatrick St Detroit MI 48228
O:734-743-3903 F:734-956-5903 C:734-751-5978