



DAVE POMAVILLE & SONS, INC.
Roofing & Sheet Metal Work
7233 E. Eight Mile Road
Warren, Michigan 48091

9736

PROPOSAL

PHONE: 586/755-6030 FAX: 586/755-2776 pomavilleroofing.net

TO Brown, Gracie
1101 Chicago Blvd.
Detroit, MI. 48202

PHONE 313/600-6829	DATE 9/07/22
JOB NAME / LOCATION	
JOB NUMBER	JOB PHONE

We hereby submit specifications and estimates for:

RE: Leak at the Northeast Chimney

1. Remove the tiles around the four sides of the chimney and save tiles.
2. Remove all existing chimney flashings, saddle, and underlayments and haul debris from the job site.
3. Repair the rotted soffit boards on the left side of the chimney and roof boards, as needed.
4. Install Ice & Water Shield followed by a 30# felt underlayment.
5. Fabricate and install all necessary 16oz copper chimney flashings and saddle.
6. Properly cap flash the chimney and seal to the masonry using silicone caulking.
7. Re-install the tiles that were removed.

Labor & Materials.....\$5,846.00

JOB WAS ESTIMATED BY CLIFF NOVELLY.

FAMILY OWNED AND OPERATED SINCE 1947

We Propose hereby to furnish material and labor — complete in accordance with the above specifications, for the sum of:
Five Thousand Eight Hundred Forty Six and 00/100 Dollars dollars (\$) **5846.00** .

Payment to be made as follows:

A 50% deposit, balance due upon completion. 1-1/2% interest per month on unpaid balance due after thirty days from the date of the invoice.
Make any checks payable to: **DAVE POMAVILLE & SONS, INC.**

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation Insurance.

Authorized Signature _____

Note: This proposal may be withdrawn by us if not accepted within **30** days.

Acceptance of Proposal — The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Signature _____

Date of Acceptance: _____

9734



DAVE POMAVILLE & SONS, INC.

Roofing & Sheet Metal Work

7233 E. Eight Mile Road

Warren, Michigan 48091

PROPOSAL

PHONE: 586/755-6030 FAX: 586/755-2776 pomavilleroofing.net

TO Brown, Gracie 1101 Chicago Blvd. Detroit, MI. 48202	PHONE 313/600-6829	DATE 9/07/22
	JOB NAME / LOCATION	
	JOB NUMBER	JOB PHONE

We hereby submit specifications and estimates for:

RE: Leak at the Southwest Dormer (Both sides of the Dormer)

1. Remove the tiles three feet wide along the dormer sidewalls and save tiles.
2. Remove the tile on the dormer sidewalls, as needed, and save tiles.
3. Remove the existing underlayment and sidewall flashings and haul debris from the job site.
4. Inspect the roof boards and repair, if needed, on a unit price basis of \$6.50 per lineal foot on roof boards.
5. Install Ice & Water Shield followed by a 30# felt underlayment.
6. Fabricate and install a new 16oz copper dormer sidewall flashing.
7. Re-install the tiles that were removed and replace any of the pieces that were broken upon removal with new pieces of tile.
8. Inspect the metal barrel roof dormer and make minor repairs (if needed);

NOTE: Owner shall be notified as to the condition of the barrel roof.

Labor & Materials.....\$5,547.00

NOTE: A tile roof is dependent upon the underlayment, the owner will be notified as to the condition of the existing underlayment.

JOB WAS ESTIMATED BY CLIFF NOVELLY.

FAMILY OWNED AND OPERATED SINCE 1947

We Propose hereby to furnish material and labor — complete in accordance with the above specifications, for the sum of: Five Thousand Five Hundred Forty Seven and 00/100 Dollars dollars (\$) 5547.00).

Payment to be made as follows:
A 50% deposit, balance due upon completion. 1-1/2% interest per month on unpaid balance due after thirty days from the date of the invoice.
Make any checks payable to: DAVE POMAVILLE & SONS, INC.

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation Insurance.

Authorized Signature _____

Note: This proposal may be withdrawn by us if not accepted within 30 days.

Acceptance of Proposal — The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Signature _____

Date of Acceptance: _____

9736



DAVE POMAVILLE & SONS, INC.
 Roofing & Sheet Metal Work
 7233 E. Eight Mile Road
 Warren, Michigan 48091

PROPOSAL

PHONE: 586/755-6030 FAX: 586/755-2776 pomavilleroofing.net

TO Brown, Gracie 1101 Chicago Blvd. Detroit, MI. 48202	PHONE 313/600-6829	DATE 9/07/22
	JOB NAME / LOCATION	
	JOB NUMBER	JOB PHONE

We hereby submit specifications and estimates for:

RE: Leak at the Northeast Chimney

1. Remove the tiles around the four sides of the chimney and save tiles.
2. Remove all existing chimney flashings, saddle, and underlayments and haul debris from the job site.
3. Repair the rotted soffit boards on the left side of the chimney and roof boards, as needed.
4. Install Ice & Water Shield followed by a 30# felt underlayment.
5. Fabricate and install all necessary 16oz copper chimney flashings and saddle.
6. Properly cap flash the chimney and seal to the masonry using silicone caulking.
7. Re-install the tiles that were removed.

Labor & Materials.....\$5,846.00

JOB WAS ESTIMATED BY CLIFF NOVELLY.

FAMILY OWNED AND OPERATED SINCE 1947

We Propose hereby to furnish material and labor — complete in accordance with the above specifications, for the sum of:
 Five Thousand Eight Hundred Forty Six and 00/100 Dollars dollars (\$) 5846.00

Payment to be made as follows:

A 50% deposit, balance due upon completion. 1-1/2% interest per month on unpaid balance due after thirty days from the date of the invoice.
 Make any checks payable to: DAVE POMAVILLE & SONS, INC.

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation Insurance.

Authorized Signature _____

Note: This proposal may be withdrawn by us if not accepted within 30 days.

Acceptance of Proposal — The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature _____

Signature _____

Date of Acceptance: _____